
SUB HEAD : 15.0

DISMANTLING AND DEMOLISHING

BUILDING WORK

15.0 Dismantling and Demolishing

Item No.	Description	Unit	Qty	Rate	Rate Code.	Cost Rs.
15.1	Demolishing iime concrete and disposal of material within 50 metre lead. Details of cost for 1 cum					
	Labour:					
	Beldar	per day	0.44	306.00	(0114)	134.64
	Coolie	per day	0.37	318.00	(0115)	117.66
	Sundries	1 time	1.04	2.12	(9999)	2.20
	Total					254.50
	Ada tor water charges @ 1%					2.55 (X)
	Total					257.05
	Add GST 12% on "X" (multiplying factor 0.1405)					36.12
	Total					293.17 (Y)
	Add 15 % Contractor's profit and overheads on "Y"					43.97
	Cost of 1 cum					337.14
	Add labour cess @ 1%					3.37
	Rate including labour cess					340.51
		Say		Rs.340.50	per cum	
15.2	Demolishing cement concrete including disposal of fmaterial wihin 50 metre lead:					
15.2.1	Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)					
	Details of cost for 1 cum					
	Labour:					
	Beldar	per day	1.59	306.00	(0114)	486.54
	Coolie	per day	0.72	318.00	(0115)	228.96
	Sundries	1 time	4.81	2.12	(9999)	10.20
	Total					725.70
	Ada tor water charges @ 1%					7.26 (X)
	Total					732.95
	Add GST 12% on "X" (multiplying factor 0.1405)					102.98
	Total					835.93 (Y)
	Add 15 % Contractor's profit and overheads on "Y"					125.39
	Cost of 1 cum					961.32
	Add labour cess @ 1%					9.61
	Rate including labour cess					970.93
		Say		Rs.970.90	per cum	
15.2.2	Nominal concrete 1:4:8 or leaner mix (including equivalent design mix)					
	Details of cost for 1 cum					
	Labour:					
	Beldar	per day	0.88	306.00	(0114)	269.28
	Coolie	per day	0.55	318.00	(0115)	174.90
	Sundries	1 time	1.95	2.12	(9999)	4.13
	Total					448.31
	Ada tor water charges @ 1%					4.48 (X)
	Total					452.80
	Add GST 12% on "X" (multiplying factor 0.1405)					63.62
	Total					516.42 (Y)














Item No.	Description	Unit	Qty	Rate	Rate Code.	Cost Rs.
	Add 15 % Contractor's profit and overheads on "Y"					77.46
	Cost of 1 cum					593.88
	Add labour cess @ 1%					5.94
	Rate including labour cess					599.82
			Say	Rs.599.80	per cum	
15.3	Demolishing R.C.C. work including stacking of steel bars and disposal of unserviceable material within 50 metres lead: Details of cost for 1 cum					
	Labour:					
	Beldar	per day	2.65	306.00	(0114)	810.90
	Coolie	per day	0.72	318.00	(0115)	228.96
	Sundries	1 time	7.02	2.12	(9999)	14.88
	Total					1054.74
	Add for water charges @ 1%					10.55 (X)
	Total					1065.29
	Add GST 12% on "X" (multiplying factor 0.1405)					149.67
	Total					1214.96 (Y)
	Add 15 % Contractor's profit and overheads on "Y"					182.24
	Cost of 1 cum					1397.21
	Add labour cess @ 1%					13.97
	Rate including labour cess					1411.18
			Say	Rs.1411.20	per cum	
15.4	Demolishing R.B. work including stacking of steel bars and disposal of unserviceable material within 50 metres lead:					
	Details of cost for 1 cum					
	Labour:					
	Beldar	per day	2.120	306.000	(0114)	648.72
	Coolie	per day	0.900	318.000	(0115)	286.20
	Sundries	1 time	4.680	2.120	(9999)	9.92
	Total					944.84
	Add for water charges @ 1%					9.45 (X)
	Total					954.29
	Add GST 12% on "X" (multiplying factor 0.1405)					134.08
	Total					1088.37 (Y)
	Add 15 % Contractor's profit and overheads on "Y"					163.26
	Cost of 1 cum					1251.62
	Add labour cess @ 1%					12.52
	Rate including labour cess					1264.14
			Say	Rs.1264.10	per cum	
15.5	Extra for cutting reinforcement bars in R.C.C. or R.B. work (Payment shall be made on the cross sectional area of R.C.C. or R.B. work).					
	Details of cost for 1 sqm R.C.C. or R.B. work					
	Reinforced area considering 1 % reinforcement = 0.01 sqm					
	Labour:					
	For cutting 0.01 sqm reinforcement					
	Blacksmith 2nd class	per day	0.500	369.000	(0103)	184.50
	Beldar	per day	0.500	306.000	(0114)	153.00

Item No.	Description	Unit	Qty	Rate	Rate Code.	Cost Rs.
	Sundries	1 time	13.390	2.120	(9999)	28.39
	Total					365.89
	Ada tor water cnarges @ 1%					3.66 (X)
	Total					369.55
	Add GST 12% on "X" (multiplying factor 0.1405)					51.92
	Total					421.47 (Y)
	Add 15 % Contractor's profit and overheads on "Y"					63.22
	Cost of 1 RCC					484.69
	Add labour cess @ 1%					4.85
	Rate including labour cess					489.54

Say Rs.489.50 per R.C.C

15.6 Extra for scrapping, cleaning and straightening reinforcement from R.C.C. or R.B. work. Details of cost for 10 nos. 6 metres long 16 mm dia bars@ 1.58 kg/metre

Total weight=94.80 kg=0.94S quintal

Labour:

Blacksmith 2nd class	per day	0.250	369.000	.(0103)	92.25
Beldar	per day	0.500	306.000	(0114)	153.00
Sundries	1 time	13.390	2.120	(9999)	28.39
Total					273.64
Ada tor water cnarges @ 1%					2.74 (X)
Total					276.37
Add GST 12% on "X" (multiplying factor 0.1405)					38.83
Total					315.20 (Y)
Add 15 % Contractor's profit and overheads on "Y"					47.28
Cost of 94.8 kg					362.48
Cost of 1 kg					3.82
Add labour cess @ 1%					0.04
Rate including labour cess					3.86

Say Rs.3.90 Per kg.

15.7 Demolishing brick work including stacking of serviceable material and disposal of unserviceable material within 50 metres lead:

15.7.1 In mud mortar

Details of cost for 1 cum

Labour:

Beldar	Per day	0.300	306.000	(0114)	91.80
Coolie	Per day	0.370	318.000	(0115)	117.66
Sundries	1 time	1.040	2.120	(9999)	2.20
Total					211.66
Ada tor water cnarges @ 1%					2.12 (X)
Total					213.78
Add GST 12% on "X" (multiplying factor 0.1405)					30.04
Total					243.82 (Y)
Add 15 % Contractor's profit and overheads on "Y"					36.57
Cost of 1 cum					280.39
Add labour cess @ 1%					2.80
Rate including labour cess					283.19

Sav Rs.283.20 Per cum

100 Say Rs.283.20 Per cum
 BCD/SOR_11th Edition_2022

Item No.	Description	Unit	Qty	Rate	Rate Code.	Cost Rs.
15.7.2	In lime mortar with old mughal bricks					
	Details of cost for 1 cum					
	Labour:					
	Beldar	per day	1.240	306.000	(0114)	379.44
	Coolie	per day	0.460	318.000	(0115)	146.28
	Sundries	1 time	1.040	2.120	(9999)	2.20
	Total					527.92
	Ada tor water cnarges @ 1%					5.28 (X)
	Total					533.20
	Add GST 12% on "X" (multiplying factor 0.1405)					74.92
	Total					608.12 (Y)
	Add 15 % Contractor's profit and overheads on "Y"					91.22
	Cost of 1 cum					699.34
	Add labour cess @ 1%					6.99
	Rate including labour cess					706.33
		Say		Rs.706.30	Per cum	
15.7.3	In lime mortar					
	Details of cost for 1 cum					
	Labour:					
	Beldar	per day	0.440	306.000	(0114)	134.64
	Coolie	per day	0.370	318.000	(0115)	117.66
	Sundries	1 time	1.040	2.120	(9999)	2.20
	Total					254.50
	Ada tor water cnarges @ 1%					2.55 (X)
	Total					257.05
	Add GST 12% on "X" (multiplying factor 0.1405)					36.12
	Total					293.17 (Y)
	Add 15 % Contractor's profit and overheads on "Y"					43.97
	Cost of 1 cum					337.14
	Add labour cess @ 1%					3.37
	Rate including labour cess					340.51
		Say		Rs.340.50	Per cum	
15.7.4	In cement mortar					
	Details of cost for 1 cum					
	Labour:					
	Beldar	per day	1.060	306.000	(0114)	324.36
	Coolie	per day	0.900	318.000	(0115)	286.20
	Sundries	1 time	2.400	2.120	(9999)	5.09
	Total					615.65
	Ada tor water cnarges @ 1%					6.16 (X)
	Total					621.80
	Add GST 12% on "X" (multiplying factor 0.1405)					87.36
	Total					709.17 (Y)
	Add 15 % Contractor's profit and overheads on "Y"					106.38
	Cost of 1 cum					815.54
	Add labour cess @ 1%					8.16
	Rate including labour cess					823.70
		Say		Rs.823.70	Per cum	



Item No.	Description	Unit	Qty	Rate	Rate Code.	Cost Rs.
15.8	Removing mortar form bricks and cleaning bricks including stacking within a lead of 50m (stacks of cleaned bricks shall be measured):					
15.8.1	From brick work in mud mortar					
	Details of cost for 1 cum					
	Labour:					
	Beldar	per day	2.400	306.000	(0114)	734.40
	Coolie	per day	1.600	318.000	(0115)	508.80
	Mason 2nd dass	per day	0.400	369.000	(0124)	147.60
	Sundries	1 time	1.820	2.120	(9999)	3.86
	Total					1394.66
	Ada tor water cnarges @ 1%					13.95
	Total					1408.60 (X)
	Add GST 12% on "X" (multiplying factor 0.1405)					197.91
	Total					1606.51 (Y)
	Add 15 % Contractor's profit and overheads on "Y"					240.98
	Cost of 1 cum					1847.49
	Add labour cess @ 1%					18.47
	Rate including labour cess					1865.96
		Say		Rs.1866.00	Per cum	
15.8.2	From brick work in lime mortar					
	Details of cost for 1 cum					
	Labour:					
	Betdar	per day	2.800	306.000	(0114)	856.80
	Coolie	per day	1.400	318.000	(0115)	445.20
	Mason 2nd class	per day	0.800	369.000	(0124)	295.20
	Sundries	1 time	8.970	2.120	(9999)	19.02
	Total					1616.22
	Ada tor water cnarges @ 1%					16.16
	Total					1632.38 (X)
	Add GST 12% on "X" (multiplying factor 0.1405)					229.35
	Total					1861.73 (Y)
	Add 15 % Contractor's profit and overheads on "Y"					279.26
	Cost of 1 cum					2140.99
	Add labour cess @ 1%					21.41
	Rate including labour cess					2162.40
		Say		Rs.2162.40	Per cum	
15.8.3	From brick work in cement mortar					
	Details of cost for 1 cum					
	Labour:					
	Beldar	per day	3.500	306.000	(0114)	1071.00
	Coolie	per day	1.500	318.000	(0115)	477.00
	Mason 2nd class	per day	1.240	369.000	(0124)	457.60
	Sundries	1 time	8.060	2.120	(9999)	17.09
	Total					2022.68
	Ada tor water cnarges @ 1%					20.23
	Total					2042.91 (X)
	Add GST 12% on "X" (multiplying factor 0.1405)					287.03
	Total					2329.94 (Y)
	Add 15 % Contractor's profit and overheads on "Y"					349.49
	Cost of 1 cum					2679.431
	Add labour cess @ 1%					26.79
	Rate including labour cess					2706.22
		Say		Rs.2706.20	Per cum	







102



BCD/SOR_11th Edition_ 2022

Item No.	Description	Unit	Qty	Rate	Rate Code.	Cost Rs.
15.9	Demolishing stone rubble masonry including stacking of serviceable material and disposal of unserviceable material within 50 metres lead.					
15.9.1	In lime mortar					
	Details of cost for 1 cum					
	Labour:					
	Beldar	per day	0.610	306.000	(0114)	186.66
	Coolie	per day	0.490	318.000	(0115)	155.82
	Sundries	1 time	1.950	2.120	(9999)	4.13
	Total					346.61
	Ada tor water cnarges @ 1%					3.47
	Total					350.08 (X)
	Add GST 12% on "X" (multiplying factor 0.1405)					49.19
	Total					399.27 (Y)
	Add 15 % Contractor's profit and overheads on "Y"					59.89
	Cost of 1 cum					459.16
	Add labour cess @ 1%					4.59
	Rate including labour cess					463.75
		Say		Rs.463.70	Per cum	
15.9.2	In cement mortar					
	Details of cost for 1 cum					
	Labour:					
	Beldar	per day	1.300	306.000	(0114)	397.80
	Coolie	per day	1.04	318.000	(0115)	330.72
	Sundries	1 time	2.73	2.120	(9999)	5.79
	Total					734.31
	Ada tor water cnarges @ 1%					7.34
	Total					741.65 (X)
	Add GST 12% on "X" (multiplying factor 0.1405)					104.20
	Total					845.85 (Y)
	Add 15 % Contractor's profit and overheads on "Y"					126.88
	Cost of 1 cum					972.73
	Add labour cess @ 1%					9.73
	Rate including labour cess					982.46
		Say		Rs.982.50	Per cum	
15.10	Desmantiling dressed stone work ashlar face stone work, marble work or precast concrete work including stacking of service able and disposal of unserviceable material within 50 metres lead:					
15.10.1	In lime mortar					
	Details of cost for 1 cum					
	Labour:					
	Beldar	per day	0.78	306.000	(0114)	238.68
	Coolie	per day	0.61	318.000	(0115)	193.98
	Sundries	1 time	2.73	2.120	(9999)	5.79
	Total					438.45
	Ada tor water cnarges @ 1%					4.38
	Total					442.83 (X)
	Add GST 12% on "X" (multiplying factor 0.1405)					62.22
	Total					505.05 (Y)
	Add 15 % Contractor's profit and overheads on "Y"					75.76
	Cost of 1 cum					580.81
	Add labour cess @ 1%					5.81
	Rate including labour cess					586.62
		Say		Rs.586.60	Per cum	

Item No.	Description	Unit	Qty	Rate	Rate Code.	Cost Rs.
15.10.2	In cement mortar					
	Details of cost for 1 cum					
	Labour:					
	Beldar	per day	1.55	306.000	(0114)	474.30
	Coolie	per day	1.19	318.000	(0115)	378.42
	Sundries	1 time	2.73	2.120	(9999)	5.79
	Total					858.51
	Ada tor water cnarges @ 1%					8.59
	Total					867.09 (X)
	Add GST 12% on "X" (multiplying factor 0.1405)					121.83
	Total					988.92 (Y)
	Add 15 % Contractor's profit and overheads on "Y"					148.34
	Cost of 1 cum					1137.26
	Add labour cess @ 1%					11.37
	Rate including labour cess					1148.63

Say Rs.1148.60 Per cum

15.11 Removing mortar form stones and cleaning stones and concrete articles (net quantity of stacks of cleaned materials will be measured)**15.11.1 In lime mortar**

Details of cost for 1 cum

Labour:

Mason 2nd dass	per day	0.05	369.000	(0124)	18.45
Beldar	per day	0.2	306.000	(0114)	61.20
Coolie	per day	0.2	318.000	(0115)	63.60
Sundries	1 time	0.52	2.120	(9999)	1.10
Total					144.35
Ada tor water cnarges @ 1%					1.44
Total					145.80 (X)
Add GST 12% on "X" (multiplying factor 0.1405)					20.48
Total					166.28 (Y)
Add 15 % Contractor's profit and overheads on "Y"					24.94
Cost of 1 cum					191.22
Add labour cess @ 1%					1.91
Rate including labour cess					193.13

Say Rs.193.13 Per cum

15.11.2 In cement mortar

Details of cost for 1 cum

Labour:

Mason 2nd class	per day	0.050	369.000	(0124)	18.45
Beldar	per day	0.400	306.000	(0114)	122.40
Coolie	per day	0.200	318.000	(0115)	63.60
Sundries	1 time	0.910	2.120	(9999)	1.93
Total					206.38
Ada tor water cnarges @ 1%					2.06
Total					208.44 (X)
Add GST 12% on "X" (multiplying factor 0.1405)					29.29
Total					237.73 (Y)
Add 15 % Contractor's profit and overheads on "Y"					35.66
Cost of 1 cum					273.39
Add labour cess @ 1%					2.73
Rate including labour cess					276.12

Say Rs.276.10 Per cum









Item No.	Description	Unit	Qty	Rate	Rate Code.	Cost Rs.
15.12	Desmantiling doors windows and clerestory windows (steel or wood) shutters including chowkhats, architrage. holdfasts etc. comploete and stacking within 50 metres lead:					
15.12.1	Of area 3 sqm and below					
	Details of cost for each					
	Labour:					
	Mason 2nd class	per day	0.100	369.000	(0124)	36.90
	Beldar	per day	0.180	306.000	(0114)	55.08
	blacksmith 2nd dass	per day	0.050	369.000	(0103)	18.45
	Sundries	1 time	1.430	2.120	(9999)	3.03
	Total					113.46
	Ada tor water cnarges @ 1%					1.13
	Total					114.60 (X)
	Add GST 12% on "X" (multiplying factor 0.1405)					16.10
	Total					130.70 (Y)
	Add 15 % Contractor's profit and overheads on "Y"					19.60
	Cost of 1 each					150.30
	Add labour cess @ 1%					1.50
	Rate including labour cess					151.80
		Say		Rs.151.80	Each	
15.12.2	Of area beyond 3 sqm					
	Details of cost of each					
	Labour:					
	Mason 2nd class	per day	0.130	369.000	(0124)	47.97
	Beldar	per day	0.250	306.000	(0114)	76.50
	Blacksmith 2nd dass	per day	0.070	369.000	(0103)	25.83
	Sundries	1 time	2.730	2.120	(9999)	5.79
	Total					156.09
	Ada tor water cnarges @ 1%					1.56
	Total					157.65 (X)
	Add GST 12% on "X" (multiplying factor 0.1405)					22.15
	Total					179.80 (Y)
	Add 15 % Contractor's profit and overheads on "Y"					26.97
	Cost of 1 each					206.77
	Add labour cess @ 1%					2.07
	Rate including labour cess					208.84
		Say		Rs.208.80	Each	
15.13	Taking out doors, windows and clerstory window shutters (steel or wood) including stacking within 50 metres lead.					
15.13.1	Of area 3 sqm and below					
	Details of cost of each					
	Labour:					
	Carpenter 2nd class	per day	0.050	369.000	(0112)	18.45
	Beldar	per day	0.080	306.000	(0114)	24.48
	Sundries	1 time	0.520	2.120	(9999)	1.10
	Total					44.03
	Ada tor water cnarges @ 1%					0.44
	Total					44.47 (X)
	Add GST 12% on "X" (multiplying factor 0.1405)					6.25
	Total					50.72 (Y)
	Add 15 % Contractor's profit and overheads on "Y"					7.61
	Cost of 1 each					58.33
	Add labour cess @ 1%					0.58
	Rate including labour cess					58.91
		Say		Rs.58.90	Each	

Item No.	Description	Unit	Qty	Rate	Rate Code.	Cost Rs.
15.15	Extra for dismantling trusses, rafters, purlins etc. of wood work for every additional span of of one metre or part thereof beyond 10 metres:					
15.15.1	Of sectional area 40 cm² and above					
	Details of cost for 1 cum for every additional span of 1 metre.					
	Labour:					
	Blacksmith 2nd dass	per day	0.200	369.000	(0103)	73.80
	Beldar	per day	0.300	306.000	(0114)	91.80
	Sundries	1 time	13.390	2.120	(9999)	28.39
	Total					193.99
	Ada tor water cnarges @ 1%					1.94
	Total					195.93 (X)
	Add GST 12% on "X" (multiplying factor 0.1405)					27.53
	Total					223.45 (Y)
	Add 15 % Contractor's profit and overheads on "Y"					33.52
	Cost of 1 metre span					256.97
	Add labour cess @ 1%					2.57
	Rate including labour cess					259.54
	Cost of 1.00 cum per metre span		Say	Rs.259.50		per cum per m span
15.15.2	Of. sectional area below 40 cm²					
	Details of cost for 1.00 cum for every additional span of 1.00 metre					
	Labour:					
	Blacksmith 2nd class	per day	0.007	369.000	(0103)	2.399
	Beldar	per day	0.008	306.000	(0114)	2.448
	Sundries	1 time	0.390	2.120	(9999)	0.827
	Total					5.673
	Ada tor water cnarges @ 1%					0.057
	Total					5.730 (X)
	Add GST 12% on "X" (multiplying factor 0.1405)					0.805
	Total					6.535 (Y)
	Add 15 % Contractor's profit and overheads on "Y"					0.980
	Cost of 10 m					7.515
	Cost of 1 metre span					0.752
	Add labour cess @ 1%					0.010
	Rate including labour cess					0.762
	Cost of 1.00 metre per metre span		Say	Rs.0.80		per metre per m span
15.16	Extra for dismantling trusses, rafters purlins etc. of wood work for every additional height of one metre or part thereof beyond 5 metres.					
15.16.1	Of sectional area 40 square centimetres and above					
	Details of cost for 1 cum/m					
	Labour:					
	Blacksmith 2nd class	per day	0.250	369.000	(0103)	92.25
	Beldar	per day	0.500	306.000	(0114)	153.00
	Sundries	1 time	13.390	2.120	(9999)	28.39
	Total					273.64
	Ada tor water cnarges @ 1%					2.74
	Total					276.37 (X)
	Add GST 12% on "X" (multiplying factor 0.1405)					38.83
	Total					315.20 (Y)
	Add 15 % Contractor's profit and overheads on "Y"					47.28
	Cost of 1 cum					362.48

Item No.	Description	Unit	Qty	Rate	Rate Code.	Cost Rs.
	Add labour cess @ 1%					3.62
	Rate including labour cess					366.10
	Cost of 1.00 cum per metre height		Say	Rs.366.10		per cum/m ht.
15.16.2	Of sectional area belwo 40 square centimetres					
	Details of cost for 10 metre per additional height of 1 metre					
	Labour:					
	Blacksmith 2nd class	per day	0.01	369.000	(0103)	3.690
	Beldar	per day	0.02	306.000	(0114)	6.120
	Sundries	1 time	0.39	2.120	(9999)	0.827
	Total					10.637
	Ada tor water cnarges @ 1%					0.106
	Total					10.743 (X)
	Add GST 12% on "X" (multiplying factor 0.1405)					1.509
	Total					12.253 (Y)
	Add 15 % Contractor's profit and overheads on "Y"					1.838
	Cost of 10 m					14.090
	Cost of 1 m					1.409
	Add labour cess @ 1%					0.010
	Rate including labour cess					1.419
	Cost of 1.00 metre per metre height		Say	Rs.1.40		metre per metre ht
15.17	Dismantling steel work in single sections including desmembering and stacking-within SO metres lead in:					
15.17.1	R.S. Joists					
	Details of cost for 1 quintal					
	Labour:					
	Blacksmith 2nd dass	per day	0.050	369.000	(0103)	18.45
	Bandhani	per day	0.100	325.000	(0100)	32.50
	Beldar	per day	0.150	306.000	(0114)	45.90
	Sundries	1 time	2.730	2.120	(9999)	5.79
	Total					102.64
	Ada tor water cnarges @ 1%					1.03
	Total					103.66 (X)
	Add GST 12% on "X" (multiplying factor 0.1405)					14.56
	Total					118.23 (Y)
	Add 15 % Contractor's profit and overheads on "Y"					17.73
	Cost of 100 kg					135.96
	Cost of 1 kg					1.36
	Add labour cess @ 1%					0.01
	Rate including labour cess					1.37
			Say	Rs.1.40		per kg
15.17.2	Channels.angles, tees and flats					
	Details of cost for 1 quintal					
	Labour:					
	Blacksmith 2nd dass	per day	0.050	369.000	(0103)	18.450
	Bandhani	per day	0.050	325.000	(0100)	16.25
	Beldar	per day	0.100	306.000	(0114)	30.60
	Sundries	1 time	2.730	2.120	(9999)	5.79
	Total					71.09
	Ada tor water cnarges @ 1%					0.71
	Total					71.80 (X)
	Add GST 12% on "X" (multiplying factor 0.1405)					10.09















Item No.	Description	Unit	Qty	Rate	Rate Code.	Cost Rs.
	Total					81.89 (Y)
	Add 15 % Contractor's profit and overheads on "Y"					12.28
	Cost of 100 kg					94.17
	Cost of 1 kg					0.94
	Add labour cess @ 1%					0.01
	Rate including labour cess					0.95
	Say Rs.1.00 per kg					
15.18	Dismantling steel work in built up sections in angles, tees, flats and channels including all gusset plates, bolts, nuts, cutting rivets, welding etc. including dismantling and stacking within 50 metres lead.					
	Details of cost for 1 quintal					
	Labour:					
	Blacksmith 2nd class	per day	0.150	369.000	(0103)	55.35
	Bandhani	per day	0.100	325.000	(0100)	32.50
	Beldar	per day	0.250	306.000	(0114)	76.50
	Sundries	1 time	4.160	2.120	(9999)	8.82
	Total					173.17
	Add for water charges @ 1%					1.73
	Total					174.90 (X)
	Add GST 12% on "X" (multiplying factor 0.1405)					24.57
	Total					199.47 (Y)
	Add 15 % Contractor's profit and overheads on "Y"					29.92
	Cost of 100 kg					229.40
	Cost of 1 kg					2.29
	Add labour cess @ 1%					0.02
	Rate including labour cess					2.31
	Say Rs.2.30 per kg					
15.19	Dismantling steel work in built up sections without dismantling and stacking within 50 metres lead Details of cost for 1 quintal					
	Labour:					
	Bandhani	per day	0.100	325.000	(0100)	32.50
	Beldar	per day	0.250	306.000	(0114)	76.52
	Sundries	1 time	2.730	2.120	(9999)	5.79
	Total					114.81
	Add for water charges @ 1%					1.15
	Total					115.96 (X)
	Add GST 12% on "X" (multiplying factor 0.1405)					16.29
	Total					132.25 (Y)
	Add 15 % Contractor's profit and overheads on "Y"					19.84
	Cost of 100 kg					152.09
	Cost of 1 kg					1.52
	Add labour cess @ 1%					0.02
	Rate including labour cess					1.54
	Say Rs.1.60 per kg					
15.20	Extra for dismantling trusses, rafters, purlins etc. Of steel work for every additional span of one metre or part thereof beyond 10 metres Details of cost for 1 quintal for every additional span of 1 metre beyond 10 m					
	Labour:					
	Bandhani	per day	0.020	325.000	(0100)	6.500
	Beldar	per day	0.060	306.000	(0114)	18.360
	Sundries	1 time	0.390	2.120	(9999)	0.827
	Total					25.687
	Add for water charges @ 1%					0.256868

Item No.	Description	Unit	Qty	Rate	Rate Code.	Cost Rs.
	Total					25.943668 (X)
	Add GST 12% on "X" (multiplying factor 0.1405)					3.65
	Total					29.59 (Y)
	Add 15 % Contractor's profit and overheads on "Y"					4.44
	Cost of 100 kg					34.03
	Cost of 1 kg					0.34
	Add labour cess @ 1%					0.00
	Rate including labour cess					0.34
		Say		Rs.0.30	per kg	
15.21	Extra for dismantling trusses, rafters, purlins etc. Of steel work for every additional height of one metre or part there of beyond 5 metres Details of cost per quintal / metre					
	Labour:					
	Bandhani	per day	0.020	325.000	(0100)	6.500
	Beldar	per day	0.060	306.000	(0114)	18.360
	Sundries	1 time	0.390	2.120	(9999)	0.827
	Total					25.687
	Ada tor water cnarges @ 1%					0.256868
	Total					25.943668 (X)
	Add GST 12% on "X" (multiplying factor 0.1405)					3.65
	Total					29.59 (Y)
	Add 15 % Contractor's profit and overheads on "Y"					4.44
	Cost of 100 kg					34.03
	Cost of 1 kg					0.34
	Add labour cess @ 1%					0.00
	Rate including labour cess					0.34
		Say		Rs.0.30	per kg	
15.22	Extra for marking of structural steel work required to be re-erected.					
	Details of cost fper.quinta!					
	Labour:					
	Mistry	per day	0.200	306.000	(0130)	61.2
	Beldar	per day	0.200	306.000	(0114)	61.2
	Total					122.400
	Ada tor water cnarges @ 1%					1.224
	Total					123.624 (X)
	Add GST 12% on "X" (multiplying factor 0.1405)					17.37
	Total					140.99 (Y)
	Add 15 % Contractor's profit and overheads on "Y"					21.15
	Cost of 100 kg					162.142
	Cost of 1 kg					1.62
	Add labour cess @ 1%					0.02
	Rate including labour cess					1.64
		Say		Rs.1.60	per kg	
15.23	Dismantling tile work in floorss and roofs laindin cement mortar including stacking material within 50 metres lead.					
15.23.1	For thickness of tiles 10 mm to 25 mm					
	Details of cost for 10 sqm					
	Labour: Mason 2nd class	per day	0.300	369.000	(0124)	110.70
	Beldar	per day	0.120	306.000	(0114)	36.72
	Coolie	per day	0.240	318.000	(0115)	76.32
	Sundries	1 time	2.730	2.120	(9999)	5.79
	Total					229.53






Item No.	Description	Unit	Qty	Rate	Rate Code.	Cost Rs.
	Ada tor water cnarges @ 1%					2.30
	Total					231.82 (X)
	Add GST 12% on "X" (multiplying factor 0.1405)					32.57
	Total					264.39 (Y)
	Add 15 % Contractor's profit and overheads on "Y"					39.66
	Cost of 10 sqm					304.05
	Cost of 1 sqm					30.41
	Add labour cess @ 1%					0.30
	Rate including labour cess					30.71
			Say	Rs.30.70	Per sqm	

15.23.2 For thickness of tiles above 25 mm and upto 40 mm

Details of cost for 10 sqm

Labour:

Mason 2nd class	per day	0.590	369.000	(0124)	217.71
Beldar	per day	0.180	306.000	(0114)	55.08
Coolie	per day	0.240	318.000	(0115)	76.32
Sundries	1 time	2.730	2.120	(9999)	5.79
Total					354.90
Ada tor water cnarges @ 1%					3.55
Total					358.45 (X)
Add GST 12% on "X" (multiplying factor 0.1405)					50.36
Total					408.81 (Y)
Add 15 % Contractor's profit and overheads on "Y"					61.32
Cost of 10 sqm					470.13
Cost of 1 sqm					47.01
Add labour cess @ 1%					0.47
Rate including labour cess					47.48

Say Rs.47.50 Per sqm

15.24 Demolishing dry brick pitching in floors, drains etc. including stacking serviceable material and disposal of unserviceable material within 50 metres lead.

Details of cost for 1 cum

Labour:

Beldar	per day	0.250	306.000	(0114)	76.50
Coolie	per day	1.000	318.000	(0115)	318.00
Sundries	1 time	2.730	2.120	(9999)	5.79
Total					400.29
Ada tor water cnarges @ 1%					4.00
Total					404.29 (X)
Add GST 12% on "X" (multiplying factor 0.1405)					56.80
Total					461.09 (Y)
Add 15 % Contractor's profit and overheads on "Y"					69.16
Cost of 1 cum					530.26
Add labour cess @ 1%					5.30
Rate including labour cess					535.56

Say Rs.535.60 Per sqm

15.25 Dismantling stone slab flooring laid in cement mortar including stacking of serviceable material and disposal of unserviceable material within 50 metres lead.

Details of cost for 10 sqm

Labour:

Beidar	per day	1.770	306.000	(0114)	541.62
Coolie	per day	0.750	318.000	(0115)	238.50
Sundries	1 time	8.060	2.120	(9999)	17.09
Total					797.21

Item No.	Description	Unit	Qty	Rate	Rate Code.	Cost Rs.
	Ada tor water cnarges @ 1%					7.97
	Total					805.18 (X)
	Add GST 12% on "X" (multiplying factor 0.1405)					113.13
	Total					918.31 (Y)
	Add 15 % Contractor's profit and overheads on "Y"					137.75
	Cost of 10 sqm					1056.05
	Cost of 1 sqm					105.61
	Add labour cess @ 1%					1.06
	Rate including labour cess					106.67

Say Rs.106.70 Per sqm

15.26 Demolishing brick tile covering in terracing including stacking of serviceable material and disposal of unserviceable material within 50 metres lead.

Details of cost for 10.00 sqm

Labour:

Mason 2nd class	per day	0.540	369.000	(0124)	199.26
Beidar	per day	0.160	306.000	(0114)	48.96
Coolie	per day	0.240	318.000	(0115)	76.32
Sundries	1 time	2.470	2.120	(9999)	5.24
Total					329.78
Ada tor water cnarges @ 1%					3.30
Total					333.07 (X)
Add GST 12% on "X" (multiplying factor 0.1405)					46.80
Total					379.87 (Y)
Add 15 % Contractor's profit and overheads on "Y"					56.98
Cost of 10 sqm					436.85
Cost of 1 sqm					43.69
Add labour cess @ 1%					0.44
Rate including labour cess					44.13

Say Rs.44.10 Per sqm

15.27 Demolishing mud phaska in terracing and disposal of material within 50 metres lead

Details of cost for 1 cum

Labour:

Beidar	per day	0.250	306.000	(0114)	76.50
Coolie	per day	0.620	318.000	(0115)	197.16
Sundries	1 time	1.040	2.120	(9999)	2.20
Total					275.86
Ada tor water cnarges @ 1%					2.76
Total					278.62 (X)
Add GST 12% on "X" (multiplying factor 0.1405)					39.15
Total					317.77 (Y)
Add 15 % Contractor's profit and overheads on "Y"					47.67
Cost of 1 cum					365.44
Add labour cess @ 1%					3.65
Rate including labour cess					369.09

Say Rs.369.10 Per cum


15.28 Dismantling roofing including ridges, hips valleys and gutters etc. and stacking the material within 50 metres lead of:

15.28.1 G.S. Sheet

Details of cost for 10 sqm

Labour:

Carpenter 2nd class	per day	0.500	369.000	(0112)	184.50
Beidar	per day	1.000	306.000	(0114)	306.00
Sundries	1 time	6.760	2.120	(9999)	14.33


 112  BCD/SOR_11th Edition_2022

Item No.	Description	Unit	Qty	Rate	Rate Code.	Cost Rs.
	Total					504.83
	Ada tor water cnarges @ 1%					5.05
	Total					509.88 (X)
	Add GST 12% on "X" (multiplying factor 0.1405)					71.64
	Total					581.52 (Y)
	Add 15 % Contractor's profit and overheads on "Y"					87.23
	Cost of 10 sqm					668.75
	Cost of 1 sqm					66.87
	Add labour cess @ 1%					0.67
	Rate including labour cess					67.54

Say Rs.67.50 Per sqm

15.28.2 Asbestos sheet

Details of cost for 10 sqm

Labour:

Carpenter 2nd class	per day	0.200	369.000	(0112)	73.80
Beldar	per day	0.500	306.000	(0114)	153.00
Sundries	1 time	5.330	2.120	(9999)	11.30
Total					238.10
Ada tor water cnarges @ 1%					2.38
Total					240.48 (X)
Add GST 12% on "X" (multiplying factor 0.1405)					33.79
Total					274.27 (Y)
Add 15 % Contractor's profit and overheads on "Y"					41.14
Cost of 10-sqm					315.41
Cost of 1 sqm					31.54
Add labour cess @ 1%					0.32
Rate including labour cess					31.86

Say Rs.31.90 Per sqm

15.29 Dismantling stone slab roofing over wooden karries or R.C.C battens (dismantling karries and battens to be paid for separately) including stacking of serviceable material and disposal of unserviceable material within 50 metres lead:

Details of cost for 1 cum

Labour:

Beldar	per day	1.770	306.000	(0114)	541.62
Coolie	per day	0.750	318.000	(0115)	238.50
Sundries	1 time	8.060	2.120	(9999)	17.09
Total					797.21
Ada tor water cnarges @ 1%					7.97
Total					805.18 (X)
Add GST 12% on "X" (multiplying factor 0.1405)					113.13
Total					918.31 (Y)
Add 15 % Contractor's profit and overheads on "Y"					137.75
Cost of 1 cum					1056.05
Add labour cess @ 1%					10.56
Rate including labour cess					1066.61

Say Rs.1066.60 Per cum

15.30 Dismantling jack arch roofing and floors including stacking of serviceable material and disposal of unserviceable material within 50 metres lead.

Details of cost for 10 sqm

Labour:

Beldar	per day	1.190	306.000	(0114)	364.14
Coolie	per day	1.210	318.000	(0115)	384.78
Sundries	1 time	8.060	2.120	(9999)	17.09

Item No.	Description	Unit	Qty	Rate	Rate Code.	Cost Rs.
	Total					766.01
	Ada tor water cnarges @ 1%					7.66
	Total					773.67 (X)
	Add GST 12% on "X" (multiplying factor 0.1405)					108.70
	Total					882.37 (Y)
	Add 15 % Contractor's profit and overheads on "Y"					132.36
	Cost of 10 sqm					1014.72
	Cost of 1 sqm					101.47
	Add labour cess @ 1%					1.01
	Rate including labour cess					102.48

Say Rs.102.50 Per sqm

15.31 Dismantling tiled roofing with battens boarding etc. complete including stacking of serviceable material and disposal of unserviceable material within 50 metres lead.

Details of cost for TO sqm

Labour:

Beldar	per day	1.730	306.000	(0114)	529.38
Coolie	per day	0.250	318.000	(0115)	79.50
Sundries	1 time	8.060	2.120	(9999)	17.09
Total					625.97
Ada tor water cnarges @ 1%					6.26
Total					632.23 (X)
Add GST 12% on "X" (multiplying factor 0.1405)					88.83
Total					721.05 (Y)
Add 15 % Contractor's profit and overheads on "Y"					108.16
Cost of 10 sqm					829.21
Cost of 1 sqm					82.92
Add labour cess @ 1%					0.83
Rate including labour cess					83.75

Say Rs.83.80 Per sqm

15.32 Demolishing thatch roofing including mats.bamboojaffari etc, complete including stacking of servicable material and disposal of unserviceable material within 50 metres lead Details of cost for 10 sqm

Labour:

Beldar	per day	0.540	306.000	(0114)	165.24
Sundries	1 time	3.640	2.120	(9999)	7.72
Total					172.96
Ada tor water cnarges @ 1%					1.73
Total					174.69 (X)
Add GST 12% on "X" (multiplying factor 0.1405)					24.54
Total					199.23 (Y)
Add 15 % Contractor's profit and overheads on "Y"					29.88
Cost of 10 sqm					229.11
Cost of 1 sqm					22.91
Add labour cess @ 1%					0.23
Rate including labour cess					23.14

Say Rs.23.10 Per sqm

15.33 Dismanting wooden bailies in posts and struts including stacking within 50 metres lead Details of cost for 10 sqm

Labour:

Beldar	per day	0.500	306.000	(0114)	153.000
Coolie	per day	0.500	318.000	(0115)	159.000
Sundries	1 time	0.520	2.120	(9999)	1.102
Total					313.102














Item No.	Description	Unit	Qty	Rate	Rate Code.	Cost Rs.
	Ada tor water cnarges @ 1%					3.131
	Total					316.233 (X)
	Add GST 12% on "X" (multiplying factor 0.1405)					44.431
	Total					360.664 (Y)
	Add 15 % Contractor's profit and overheads on "Y"					54.100
	Cost of 50 m					414.764
	Cost of 1 m					8.295
	Add labour cess @ 1%					0.080
	Rate including labour cess					8.375
		Say		Rs.8.40	Per sqm	
15.34	Dismantling and stacking 50 metres lead.fencing posts or struts including all earth work and dismantling of concrete etc. in base of:					
15.34.1	T' or 'L' iron or pipe					
	Details of cost for 1 each					
	Labour:					
	Beldar	per day	0.107	306.000	(0114)	32.74
	Coolie	per day	0.067	318.000	(0115)	21.31
	Excavation , transporting and stacking the posts to the required place within 50 metres lead, refilling the pit and dressing the same	1 time	0.260	2.120	(9999)	0.55
	Extra for lifting of R.C.C. posts being heavier than L iron and cleaning the posts of stacking concrete	1 time	13.390	2.120	(9999)	28.39
	Sundries	1 time	1.430	2.120	(9999)	3.03
	Total					86.02
	Ada tor water cnarges @ 1%					0.86
	Total					86.88 (X)
	Add GST 12% on "X" (multiplying factor 0.1405)					12.21
	Total					99.08 (Y)
	Add 15 % Contractor's profit and overheads on "Y"					14.86
	Cost of 1 each					113.95
	Add labour cess @ 1%					1.14
	Rate including labour cess					115.09
		Say		Rs.115.10	Each	
15.34.2	R.C. C.					
	Details of cost for 1 each					
	Labour:					
	Beldar	per day	0.097	306.000	(0114)	29.68
	Coolie	per day	0.060	318.000	(0115)	19.08
	Sundres	1 time	0.260	2.120	(9999)	0.55
	Excavation , transporting and stacking the posts to the requied place within metres lead, refilling the pit and dresing the same	1 time	13.390	2.120	(9999)	28.39
	Extra for lifting or R.C.C. posts being heavier than L iron and cleaning the posts of stacking concrete	1 time	8.060	2.120	(9999)	17.09
	Sundries	1 time	2.730	2.120	(9999)	5.79
	Total					100.57
	Ada tor water cnarges @ 1%					1.01
	Total					101.58 (X)

Item No.	Description	Unit	Qty	Rate	Rate Code.	Cost Rs.
	Add GST 12% on "X" (multiplying factor 0.1405)					14.27
	Total					115.85 (Y)
	Add 15 % Contractor's profit and overheads on "Y"					17.38
	Cost of 1 each					133.23
	Add labour cess @ 1%					1.33
	Rate including labour cess					134.56

Say Rs.134.57 Each

15.35 Cutting bairies or wooden posts of fencing at the point of projection above the concrete or ground and stacking the same within 50 metres lead. Details of cost for 1 bailie (post)

Cutting	1 time	2.730	2.120	(9999)	5.79
Transporting and stacking	1 time	1.430	2.120	(9999)	3.03
Total					8.82
Ada tor water cnarges @ 1%					0.09
Total					8.91 (X)
Add GST 12% on "X" (multiplying factor 0.1405)					1.25
Total					10.16 (Y)
Add 15 % Contractor's profit and overheads on "Y"					1.52
Cost of 1 each					11.68
Add labour cess @ 1%					0.12
Rate including labour cess					11.80

Say Rs.11.80 Each

15.36 Dismantling barbed wire or flexible rope in fencing including making rolls and stacking within 50 metres lead.

Details of cost for pne quintal

Labour:

Beldar	per day	3.500	306.000	(0114)	1071.00
Sundries	1 time	5.330	2.120	(9999)	11.30
Total					1082.30
Ada tor water cnarges @ 1%					10.82
Total					1093.12 (X)
Add GST 12% on "X" (multiplying factor 0.1405)					153.58
Total					1246.71 (Y)
Add 15 % Contractor's profit and overheads on "Y"					187.01
Cost of 100 kg					1433.71
Cost of 1 kg					14.34
Add labour cess @ 1%					0.14
Rate including labour cess					14.48


Say Rs.14.50 per kg

15.37 Dismantling wooden trellis work excluding frames but including stacking the serviceable material within 50 metres lead.

Details of cost for 10 sqm

Labour:

Mason 2nd class	per day	0.100	369.000	(0124)	36.90
Beldar	per day	0.250	306.000	(0114)	76.50
Coolie	per day	0.250	318.000	(0115)	79.50
Sundries	1 time	2.730	2.120	(9999)	5.79
Total					198.69
Ada tor water cnarges @ 1%					1.99
Total					200.67 (X)
Add GST 12% on "X" (multiplying factor 0.1405)					28.19
Total					228.87 (Y)
Add 15 % Contractor's profit and overheads on "Y"					34.33
Cost of 10sqm					263.20



Item No.	Description	Unit	Qty	Rate	Rate Code.	Cost Rs.
	Cost of 1 sqm					26.32
	Add labour cess @ 1%					0.26
	Rate including labour cess					26.58
				Say Rs.26.60	Per sqm	
15.38	Dismantling expanded metal or I.R.C. fabrics with necessary battens and beading including stacking the serviceable material within 50 metres lead.					
	Details of cost for 10 sqm					
	Labour:					
	Carpenter 2nd class	per day	0.100	369.000	(0112)	36.90
	Beldar	per day	0.400	306.000	(0114)	122.40
	Coolie	per day	0.200	318.000	(0115)	63.60
	Sundries	1 time	4.160	2.120	(9999)	8.82
	Total					231.72
	Add for water charges @ 1%					2.32
	Total					234.04 (X)
	Add GST 12% on "X" (multiplying factor 0.1405)					32.88
	Total					266.92 (Y)
	Add 15 % Contractor's profit and overheads on "Y"					40.04
	Cost of 10 sqm					306.96
	Cost of 1 sqm					30.70
	Add labour cess @ 1%					0.31
	Rate including labour cess					31.01
				Say Rs.31.00	Per sqm	
15.39	Dismantling wooden boardings in lining of walls and partitions, excluding supporting members but including stacking within 50 metres lead.					
15.39.1	Upto 10 mm thick					
	Details of cost for 10 sqm					
	Labour:					
	Carpenter 2nd class	per day	0.150	369.000	(0112)	55.35
	Beldar	per day	0.200	306.000	(0114)	61.20
	Coolie	per day	0.200	318.000	(0115)	63.60
	Sundries	1 time	5.330	2.120	(9999)	11.30
	Total					191.45
	Add for water charges @ 1%					1.91
	Total					193.36 (X)
	Add GST 12% on "X" (multiplying factor 0.1405)					27.17
	Total					220.53 (Y)
	Add 15 % Contractor's profit and overheads on "Y"					33.08
	Cost of 10 sqm					253.61
	Cost of 1 sqm					25.36
	Add labour cess @ 1%					0.25
	Rate including labour cess					25.61
				Say Rs.25.60	Per sqm	
15.39.2	Thickness above 10 mm upto 25 mm					
	Details of cost for 10 sqm					
	Labour:					
	carpenter 2nd class	per day	0.200	369.000	(0112)	73.80
	Beldar	per day	0.250	306.000	(0114)	76.50
	Coolie	per day	0.250	318.000	(0115)	79.50
	Sundries	1 time	6.760	2.120	(9999)	14.33
	Total					244.13
	Add for water charges @ 1%					2.44
	Total					246.57 (X)

Item No.	Description	Unit	Qty	Rate	Rate Code.	Cost Rs.
	Add GST 12% on "X" (multiplying factor 0.1405)					34.64
	Total					281.22 (Y)
	Add 15 % Contractor's profit and overheads on "Y"					42.18
	Cost of 10sqrh					323.40
	Cost of 1 sqm					32.34
	Add labour cess @ 1%					0.32
	Rate including labour cess					32.66
			Say	Rs.32.70	Per sqm	

15.39.3 Thickness above 25 mm upto 40 mm

Details of cost for 10 sqm						
Carpenter 2nd class	per day	0.200	369.000	(0112)		73.80
Beldar	per day	0.300	306.000	(0114)		91.80
Coolie	per day	0.300	318.000	(0115)		95.40
Sundries	1 time	13.390	2.120	(9999)		28.39
Total						289.39
Ada tor water cnarges @ 1%						2.89
Total						292.28 (X)
Add GST 12% on "X" (multiplying factor 0.1405)						41.07
Total						333.35 (Y)
Add 15 % Contractor's profit and overheads on "Y"						50.00
Cost of 10 sqm						383.35
Cost of 1 sqm						38.33
Add labour cess @ 1%						0.38
Rate including labour cess						38.71
			Say	Rs.38.70	Per sqm	

15.40 Dismanting precast concrete or stone slabs in walls , partition walls etc. including stacking within 50 metres lead.-**15.40.1 Thickness upto 40 mm**

Details of cost for 10 sqm						
Labour:						
mason 2nd class	per day	0.200	369.000	(0124)		73.80
Beldar	per day	2.000	306.000	(0114)		612.00
Coolie	per day	0.500	318.000	(0115)		159.00
Sundries	1 time	13.390	2.120	(9999)		28.39
Total						873.19
Ada tor water cnarges @ 1%						8.73
Total						881.92 (X)
Add GST 12% on "X" (multiplying factor 0.1405)						123.91
Total						1005.83 (Y)
Add 15 % Contractor's profit and overheads on "Y"						150.87
Cost of 10 sqm						1156.70
Cost of 1 sqm						115.67
Add labour cess @ 1%						1.16
Rate including labour cess						116.83
			Say	Rs.116.80	Per sqm	

15.40.2 Thickness above 40 mm upto 75 mm

Details of cost for 10 sqm						
Labour:						
mason 2nd class	per day	0.300	369.000	(0124)		110.70
Beldar	per day	3.000	306.000	(0114)		918.00
Coolie	per day	0.750	318.000	(0115)		238.50
Sundries	1 time	18.850	2.120	(9999)		39.96
Total						1307.16








118




BCD/SOR_11th Edition_ 2022

Item No.	Description	Unit	Qty	Rate	Rate Code.	Cost Rs.
	Ada tor water cnarges @ 1%					13.07
	Total					1320.23 (X)
	Add GST 12% on "X" (multiplying factor 0.1405)					185.49
	Total					1505.73 (Y)
	Add 15 % Contractor's profit and overheads on "Y"					225.86
	Cost of 10 sqm					1731.59
	Cost of 1 sqm					173.16
	Add labour cess @ 1%					1.73
	Rate including labour cess					174.89

Say Rs.174.90 Per sqm

15.41 Dismantling cement asbostors, Celotax or other hard board ceiling or partition walls including stacking of serviceable materials and disposal of unseviceabale materials within 50 metres lead. sqm

Details of cost for 10

Carpenter 2nddass	per day	0.2	369.000	(0112)	73.80
Beldar	per day	0.3	306.000	(0114)	91.80
Sundries	1 time	5.33	2.120	(9999)	11.30
Total					176.90
Ada tor water cnarges @ 1%					1.77
Total					178.67 (X)
Add GST 12% on "X" (multiplying factor 0.1405)					25.10
Total					203.77 (Y)
Add 15 % Contractor's profit and overheads on "Y"					30.57
Cost of 10 sqm					234.34
Cost of 1 sqm					23.43
Add labour cess @ 1%					0.23
Rate including labour cess					23.66

Say Rs.23.70 Per sqm

15.42 Dismantling C.I. or asbestos rain water pipe with fittings and clamps including stacking the material within 50 metres lead.

15.42.1 75 to 80 mm dia pipe .

Details of cost for 10 metres

Labour:					
Beldar	per day	0.36	306.000	(0114)	110.160
Coolie	per day	0.36	318.000	(0115)	114.480
Sundries	1 time	0.91	2.120	(9999)	1.929
Total					226.569
Ada tor water cnarges @ 1%					2.265692
Total					228.835 (X)
Add GST 12% on "X" (multiplying factor 0.1405)					32.15
Total					260.99 (Y)
Add 15 % Contractor's profit and overheads on "Y"					39.15
Cost of 10 m					300.13
Cost of 1 m					30.013
Add labour cess @ 1%					0.30
Rate including labour cess					30.31

Say Rs.30.30 per metre

15.42.2 100 mm dia pipe

Details of cost for 10 metres

Labour:					
Beldar	per day	0.36	306.000	(0114)	110.16
Coolie	per day	0.38	318.000	(0115)	120.84
Sundries	1 time	1.56	2.120	(9999)	3.31

Item No.	Description	Unit	Qty	Rate	Rate Code.	Cost Rs.
	Total					234.31
	Ada tor water cnarges @ 1%					2.34
	Total					236.65 (X)
	Add GST 12% on "X" (multiplying factor 0.1405)					33.25
	Total					269.90 (Y)
	Add 15 % Contractor's profit and overheads on "Y"					40.48
	Cost of 10 m					310.38
	Cost of 1 m					31.04
	Add labour cess @ 1%					0.31
	Rate including labour cess					31.35
		Say		Rs.31.30	per metre	

15.42.3 150 mm dia pipe

Details of cost for 10 metres

Labour:

Beldar	per day	0.36	306.000	(0114)	110.16
Coolie	per day	0.4	318.000	(0115)	127.20
Sundries	1 time	2.08	2.120	(9999)	4.41
Total					241.77
Ada tor water cnarges @ 1%					2.42
Total					244.19 (X)
Add GST 12% on "X" (multiplying factor 0.1405)					34.31
Total					278.50 (Y)
Add 15 % Contractor's profit and overheads on "Y"					41.77
Cost of 10 m					320.27
Cost of 1 m					32.03
Add labour cess @ 1%					0.32
Rate including labour cess					32.35

Say Rs.32.30 per metre

15.43 Dismanting including stacking of serviceable material and disposal of unserviceable material within 50 metres lead.**15.43.1 Water bound macadam road**

Details a road 6 metres wide and metres
length wise 25 cm average depth =9.00
cubic metre

Labour:

For cutting road taking out soling and metalling
including sorting and screening

Beldar	per day	4.800	306.000	(0114)	1468.800
Coolie	per day	2.400	318.000	(0115)	763.200
Labour for slacking of serviceable material and disposal of unserviceable material within 50 matreslead .	1 time	89.700	2.120	(9999)	190.164
Total					2422.164
Ada tor water cnarges @ 1%					24.22164
Total					2446.38564 (X)
Add GST 12% on "X" (multiplying factor 0.1405)					343.72
Total					2790.10 (Y)
Add 15 % Contractor's profit and overheads on "Y"					418.52
Cost of 36 sam					3208.618
Cost of 1 sqm					89.128
Add labour cess @ 1%					0.89
Rate including labour cess					90.02

Say Rs.90.00 Per sqm

120 BCD/SOR_11th Edition_2022

Item No.	Description	Unit	Qty	Rate	Rate Code.	Cost Rs.
15.43.2	Bituminous road					
	Details of cost for 36 sqm Consider a road 6 metres wide and 6 metres length wise 25 cm average depth = 9.00 cubic metre					
	Labour:					
	.For cutting road taking out soling and metalling including sorting and screening					
	Beldar	per day	9.600	306.000	(0114)	2937.60
	Coolie	per day	4.800	318.000	(0115)	1526.40
	Labour for stacking of serviceable material and disposal of unserviceable material within 50 metres lead.	1 time	107.640	2.120	(9999)	228.20
	Total					4692.20
	Add for water charges @ 1%					46.92
	Total					4739.12 (X)
	Add GST 12% on "X" (multiplying factor 0.1405)					665.85
	Total					5404.96 (Y)
	Add 15 % Contractor's profit and overheads on "Y"					810.74
	Cost of 36 sqm					6215.71
	Cost of 1 sqm					172.66
	Add labour cess @ 1%					1.73
	Rate including labour cess					174.39
	Say Rs.174.40 Per sqm					

15.44 Dismantling G.I. pipes (external work) including excavation and refilling trenches after taking out the pipes, manually/ by mechanical means including stacking of pipes within 50 metres lead as per direction of Engineer-in-charge :

15.44.1 15 mm to 40 mm nominal bore

Detail of cost for 10 metre

LABOUR

Trenching and refilling etc

Beldar	day	0.66	306.000	(0114)	201.96
Coolie	day	0.66	318.000	(0115)	209.88
Dismantling G.I. pipe and stacking etc	L.S.	35.88	2.120	(9999)	76.07
TOTAL					487.91 W
Add 1 % Water charges on "W"					4.88
TOTAL					492.78 X
Add GST on "X" (multiplying factor 0.1405)					69.2362442
TOTAL					562.02 Y
Add 15% CPOH on "Y"					84.30
TOTAL					646.32
Add Cess @ 1% on "Z"					6.46
Cost of 10.00 metre					652.79
Cost of 1.00 metre					65.28
Say	Say		Rs.65.30		Per Metre

15.44.2 Above 40 mm nominal bore

Detail of cost for 10 metre

LABOUR

Trenching and refilling etc

Beldar	day	0.66	306.000	(0114)	201.96
Coolie	day	0.66	318.000	(0115)	209.88

Item No.	Description	Unit	Qty	Rate	Rate Code.	Cost Rs.
	Dismantling G.I. pipe and stacking etc	L.S.	71.76	2.120	(9999)	152.13
	TOTAL					563.97 W
	Add 1 % Water charges on "W"					5.64
	TOTAL					569.61 X
	Add GST on "X" (multiplying factor 0.1405)					80.0303331
	TOTAL					649.64 Y
	Add 15% CPOH on "Y"					97.45
	TOTAL					747.09
	Add Cess @ 1% on "Z"					7.47
	Cost of 10.00 metre					754.56
	Cost of 1.00 metre					75.46
	Say		Say	Rs.75.50		Per Metre

15.45 Dismantling G.I. pipes including excavation and refilling trenches after taking out the pipes , breaking lead caulked joints, melting of lead and making into blocks including stacking of pipes , lead at site within 50 metres lead.

15.45.1 Upto 150 mm diameter

Details of cost for 40.25 m or 1 1 Nos. joints .
Earth work in excavation for dismantling
pipes including refilling of excavated earth

1x40.26x0.55x0.75 m = 16.6 cum

Deduct for pipes of average 100 mm dia = 40.26x

$(22/7)/4 \times (0.018) \times (0.018) = 0.44 \text{ cum} = 16.17 \text{ cum}$

Beldar	per day	3.230	306.000	(0114)	988.38
Coolie	per day	2.700	318.000	(0115)	858.60
Beldar	per day	1.440	306.000	(0114)	440.64
Coolie	per day	2.100	318.000	(0115)	667.80
Bhishti	per day	0.270	332.000	(0101)	89.64
Fuel wood	quintal	0.460	500.000	(0761)	230.00
Kerosine oil	litre	0.380	50.000	(0771)	19.00
Assistant fitter or 2nd class fitter	per day	0.630	369.000	(0117)	232.47
Beldar	per day	4.500	306.000	(0114)	1377.00
Carriage and sundries	1 time	53.820	2.120	(9999)	114.10
Total					5017.63
Add for water charges @ 1%					50.18
Total					5067.80 (X)
Add GST 12% on "X" (multiplying factor 0.1405)					712.03
Total					5779.83 (Y)
Add 15 % Contractor's profit and overheads on "Y"					866.97
Cost of 40.26 m					6646.81
Cost of 1 m					165.10
Add labour cess @ 1%					1.65
Rate including labour cess					166.75

Say Rs.166.70 per metre

[Handwritten signatures and initials]

Item No.	Description	Unit	Qty	Rate	Rate Code.	Cost Rs.
----------	-------------	------	-----	------	------------	----------

15.45.2 Above 150 mm dia upto 300 mm dia

Details of cost for 40.26 mor 11 Nos. joints.
Earth work in excavation for dismantling
pipes including refilling of excavated earth

1x40.26x0.65x0.75 m = 19.63 cum

Deduct for pipes of average 250 mm dia =

1x40.26x(22/7)/4x(0.274)x(0.274) = 2.37 cum , =
17.26 cum

Beldar	per day	3.450	306.00	(0114)	1055.70
Coolie	per day	2.880	318.00	(0115)	915.84
Bedar	per day	1.540	306.00	(0114)	471.24
Coolie	per day	2.240	318.00	(0115)	712.32
Bhishti	per day	0.290	332.00	(0101)	96.28
Fuel wood	quintal	1.030	500.00	(0761)	515.00
Kerosine oil	litre	1.140	50.00	(0771)	57.00
Assistant fitter or 2nd class fitter	per day	1.300	369.00	(0117)	479.70
Beldar	per day	7.500	306.00	(0114)	2295.00
Carriage and sundries	1 time	80.730	2.12	(9999)	171.15
Total					6769.23
Ada tor water cnarges @ 1%					67.69
Total					6836.92 (X)
Add GST 12% on "X" (multiplying factor 0.1405)					960.59
Total					7797.51 (Y)
Add 15 % Contractor's profit and overheads on "Y"					1169.63
Cost of 40.26 m					8967.13
Cost of 1 m					222.73
Add labour cess @ 1%					2.23
Rate including labour cess					224.96

Say Rs.225.00 per metre

15.45.3 Above 300 mm diameter

Details of cost for 40.26 mor 11 Nos. joints.
Earth work in excavation for dismantling
pipes including refilling of excavated earth

1x40.26x0.85x0.75 m = 25.67 cum

Deduct for pipes of average 450 mm dia =

1x40.26 x(22/7)/4x(0.48)x(0.48) = 7.29 cum ,
= 18.38 cum

Beldar	per day	3.680	306.000	(0114)	1126.080
Coolie	per day	3.070	318.000	(0115)	976.260
Bedar	per day	1.640	306.000	(0114)	501.840
Coolie	per day	2.390	318.000	(0115)	760.020
Bhishti	per day	0.310	332.000	(0101)	102.920
Fuel wood	quintal	1.400	500.000	(0761)	700.000
Kerosineoil	litre	2.270	50.000	(0771)	113.500
Assistant fitter or 2nd class fitter	per day	2.250	369.000	(0117)	830.250
Beldar	per day	11.500	306.000	(0114)	3519.000
Carriage and sundries	1 time	134.550	2.120	(9999)	285.246
Total					8915.116
Ada tor water cnarges @ 1%					89.15116
Total					9004.26716 (X)
Add GST 12% on "X" (multiplying factor 0.1405)					1265.10
Total					10269.37 (Y)

Item No.	Description	Unit	Qty	Rate	Rate Code.	Cost Rs.
	Add 15 % Contractor's profit and overheads on "Y"					1540.41
	Cost of 40.26 m					11809.772
	Cost of 1 m					293.338
	Add labour cess @ 1%					2.93
	Rate including labour cess					296.27
	Say Rs.296.30 per metre					
15.46	Dismantling steel cylinder R.C. pipes including excavation and refilling trenches after taking out the pipes. Breaking lead caulked joints, melting of lead and making into blocks including stacking or pipes, lead at site within 50 metres lead.					
15.46.1	Details of cost for 40.26 m or 11 Nos. joints . Earth work in excavation for dismantling pipes including refilling of excavated earth $1 \times 40.26 \times 1.3 \times 1.65 \text{ m} = 86.36 \text{ cum}$ Deduct for pipes of average 450 mm dia = $1 \times 40.26 \times (22/7) / 4 (1.00) \times (1.00) \text{ mm} = 31.63 \text{ cum}$, 54.73 cum .					
	Beldar	per day	3.680	306.000	(0114)	1126.080
	Coolie	per day	3.070	318.000	(0115)	976.260
	Bedar	per day	1.640	306.000	(0114)	501.840
	Coolie	per day	2.390	318.000	(0115)	760.020
	Bhishti	per day	0.310	332.000	(0101)	102.920
	Fuel wood	quintal	1.400	500.000	(0761)	700.000
	Kerosine oil	litre	2.270	50.000	(0771)	113.500
	Assistant fitter or 2nd class fitter	per day	2.250	369.000	(0117)	830.250
	Beldar	per day	11.500	306.000	(0114)	3519.000
	Carriage and sundries	1 time	134.550	2.120	(9999)	285.246
	Total					8915.116
	Add for water charges @ 1%					89.15116
	Total					9004.26716 (X)
	Add GST 12% on "X" (multiplying factor 0.1405)					1265.10
	Total					10269.37 (Y)
	Add 15 % Contractor's profit and overheads on "Y"					1540.41
	Cost of 40.26 m					11809.772
	Cost of 1 m					293.338
	Add labour cess @ 1%					2.93
	Rate including labour cess					296.27

Say Rs.296.30 per metre

15.46.2 Above 600 mm diameter

Details of cost for 40.26 m or 11 Nos. joints.
Earth work in excavation for dismantling pipes including refilling of excavated earth

$1 \times 40.26 \times 1.3 \times 1.65 \text{ m} = 86.36 \text{ cum}$
Deduct for pipes of average 900 mm dia =
 $1 \times 40.26 \times (22/7) (1.00) \times (1.00) \text{ m} = 31.63 \text{ cum}$. 54.73 cum

Beldar	per day	10.950	306.000	(0114)	3350.70
Coolie	per day	9.140	318.000	(0115)	2906.52
Bedar	per day	4.870	306.000	(0114)	1490.22
Coolie	per day	7.110	318.000	(0115)	2260.98
Bhishti	per day	0.930	332.000	(0101)	308.76
Fuel wood	quintal	3.080	500.000	(0761)	1540.00
Kerosine oil	litre	5.000	50.000	(0771)	250.00

124 BCD/SOR_11th Edition_2022

Item No.	Description	Unit	Qty	Rate	Rate Code.	Cost Rs.
	Assistant fitter or 2nd class fitter	per day	10.000	369.000	(0117)	3690.00
	Beldar	per day	20.000	306.000	(0114)	6120.00
	Carriage and sundries	1 time	179.400	2.120	(9999)	380.33
	Total					22297.51
	Add for water charges @ 1%					222.98
	Total					22520.48 (X)
	Add GST 12% on "X" (multiplying factor 0.1405)					3164.13
	Total					25684.61 (Y)
	Add 15 % Contractor's profit and overheads on "Y"					3852.69
	Cost of 40.26 m					29537.30
	Cost of 1 m					733.66
	Add labour cess @ 1%					7.34
	Rate including labour cess					741.00

Say Rs.741.00 per metre

15.47 Dismantling asbestos cement pressure pipes including excavation and refilling trenches after taking out the pipes and stacking the pipes within 50 metres lead .

15.47.1 Upto 150 mm diameter

Details of cost for 10 m or 11 Nos joints .

Earth work in excavation for dismantling pipes including refilling or excavated earth . 10.00 x 0.55 x 0.75 m 4.125 cum

Deduct for pipes of average 100 mm dia = $1 \times 10.00 \times (22/7) \times (0.118) \times (0.118) \text{ m} = 0.109 \text{ cum}$, 4.016 cum

Beldar	per day	0.800	306.000	(0114)	244.80
Coolie	per day	0.670	318.000	(0115)	213.06
Beldar	per day	0.360	306.000	(0114)	110.16
Coolie	per day	0.520	318.000	(0115)	165.36
Bhishti	per day	0.070	332.000	(0101)	23.24
Beldar	per day	0.360	306.000	(0114)	110.16
Coolie	per day	0.380	318.000	(0115)	120.84
Carriage and sundries	1 time	1.560	2.120	(9999)	3.31
Total					990.93
Add for water charges @ 1%					9.91
Total					1000.84 (X)
Add GST 12% on "X" (multiplying factor 0.1405)					140.62
Total					1141.45 (Y)
Add 15 % Contractor's profit and overheads on "Y"					171.22
Cost of 10 m					1312.67
Cost of 1 m					131.27
Add labour cess @ 1%					1.31
Rate including labour cess					132.58

Say Rs.132.60 per metre

15.47.2 Above 150 mm diameter

Details of cost for 10 m or 11 Nos. joints.

Earth work in excavation/or dismantling pipes including refilling of excavated earth 10.00x0.65x0.75 m = 4.88 cum

Deduct for pipes of average 250 mm dia = $1 \times 10 \times (22/7) \times (0.274) \times (0.274) = 0.590 \text{ cum} = 4.29 \text{ cum}$

Beldar	per day	0.860	306.000	(0114)	263.160
Coolie	per day	0.720	318.000	(0115)	228.960

Item No.	Description	Unit	Qty	Rate	Rate Code.	Cost Rs.
	Bedar	per day	0.380	306.000	(01 14)	116.280
	Coolie	per day	0.560	318.000	(0115)	178.080
	Bhishti	per day	0.070	332.000	(0101)	23.240
	Seldar	per day	0.360	306.000	(01 14)	110.160
	.Coolie	per day	0.880	318.000	(0115)	279.840
	Carriage and sundries	1 time	3.770	2.120	(9999)	7.992
	Total					1207.712
	Ada tor water cnarges @ 1%					12.077124
	Total					1219.78952 (X)
	Add GST 12% on "X" (multiplying factor 0.1405)					171.38
	Total					1391.17 (Y)
	Add 15 % Contractor's profit and overheads on "Y"					208.68
	Cost of 10 m					1599.845
	Cost of 1 m					159.985
	Add labour cess @ 1%					1.60
	Rate including labour cess					161.58
			Say	Rs.161.60	per metre	

15.48 Taking out C. I. cover with frame from R.C.C. top slab of manholes of various sizes including demolishing of R.C.C. work and stacking of useful materials near the site and disposal of unserviceable materials into municipal dumps within 50 metres lead.

Details of cost for one man hole
 Demolition of R.C.C. slab $1.3 \times 1.2 \times 0.15 \text{ m} = 0.234 \text{ cum}$
 Less cover $0.61 \times 0.455 \times 0.15 \text{ m} = 0.042 \text{ cum}$
 0.192 cum

Labour:

Beldar	per day	0.500	306.000	(0114)	153.00
Coolie	per day	0.140	318.000	(0115)	44.52
Removal of C.I. cover with frame including stacking	1 time	1.300	2.120	(9999)	2.76
Sundries	1 time	7.150	2.120	(9999)	15.16
Total					215.43
Ada tor water cnarges @ 1%					2.15
Total					217.59 (X)
Add GST 12% on "X" (multiplying factor 0.1405)					30.57
Total					248.16 (Y)
Add 15 % Contractor's profit and overheads on "Y"					<u>37.22</u>
Cost of 1 each					285.38
Add labour cess @ 1%					2.85
Rate including labour cess					288.23

Say Rs.288.20 Each

15.49 Taking out C.I. cover with frame from R.C.C. top slab of inspection chambers of various sizes including demolishing of R.C.C. work and stacking of useful materials near the site and disposal of unserviceable materials into municipal dumps within 50 metres

Details of cost for one man hole
Demolition of R.C.C. slab $1.1 \times 0.9 \times 0.15 \text{ m} = 0.148$
cum
Less cover $0.61 \times 0.455 \times 0.15 \text{ m} = 0.042 \text{ cum/}$
 0.106 cum
say 0.11 cum

Labour:

Beldar	per day	0.290	306.000	(0114)	88.74
Coolie	per day	0.080	318.000	(0115)	25.44

Item No.	Description	Unit	Qty	Rate	Rate Code.	Cost Rs.
	Removal of C.I. cover with frame including stacking .	1 time	0.650	2.120	(9999)	1.38
	Sundries	1 time	5.330	2.120	(9999)	11.30
	Total					126.86
	Ada tor water cnarges @ 1%					1.27
	Total					128.13 (X)
	Add GST 12% on "X" (multiplying factor 0.1405)					18.00
	Total					146.13 (Y)
	Add 15 % Contractor's profit and overheads on "Y"					21.92
	Cost of 1 each					168.05
	Add labour cess @ 1%					1.68
	Rate including labour cess					169.73
	Say Rs.169.70 Each					

15.50 Dismantling of R.C.C. spun vent shaft including excavating the cement concrete pit completely , taking out the shaft , refilling the excavated gap, stacking the useful materials near the site and disposal of unserviceable materials within 50 metres lead.

Details of cost for one

Dismanting cement concrete (a) 1:4:8

0.90x0.90x1.35m =1.094 cum

Less shaft 1/4x22/7x0.15x0.45 m = 0.024 cum .

0.919 cum

Say 0.92 cum

Dismantling cement concrete 1:2:4 0.90x0.90x0.15
= 0.122 cum

Less shaft 1/4x22/7x0.15x0.45 m = 0.024 cum/

0.098 cum

say c 10 cum

Labour:

Beldar	per day	0.810	306.000	(0114)	247.86
--------	---------	-------	---------	--------	--------

Coolie	per day	0.510	318.000	(0115)	162.18
--------	---------	-------	---------	--------	--------

Sundries	1 time	1.820	2.120	(9999)	3.86
----------	--------	-------	-------	--------	------

Beldar	per day	0.160	306.000	(0114)	48.96
--------	---------	-------	---------	--------	-------

Coolie	per day	0.070	318.000	(0115)	22.26
--------	---------	-------	---------	--------	-------

Sundries	1 time	0.520	2.120	(9999)	1.10
----------	--------	-------	-------	--------	------

Mistry	per day	0.250	306.000	(0130)	76.50
--------	---------	-------	---------	--------	-------

Mason 1 st class	per day	0.120	413.000	(0123)	49.56
------------------	---------	-------	---------	--------	-------

Mason 2nd aass	per day	0.120	369.000	(0124)	44.28
----------------	---------	-------	---------	--------	-------

Bandhani	per day	1.000	325.000	(0100)	325.00
----------	---------	-------	---------	--------	--------

Beldar	per day	1.000	306.000	(0114)	306.00
--------	---------	-------	---------	--------	--------

Sundries for scaffolding etc.	1 time	53.820	2.120	(9999)	114.10
-------------------------------	--------	--------	-------	--------	--------

Total					1401.66
-------	--	--	--	--	---------

Ada tor water cnarges @ 1%					14.02
----------------------------	--	--	--	--	-------

Total					1415.68 (X)
-------	--	--	--	--	-------------

Add GST 12% on "X" (multiplying factor 0.1405)					198.90
--	--	--	--	--	--------

Total					1614.58 (Y)
-------	--	--	--	--	-------------

Add 15 % Contractor's profit and overheads on "Y"					242.19
---	--	--	--	--	--------

Cost of 1 each					1856.76
----------------	--	--	--	--	---------

Add labour cess @ 1%					18.57
----------------------	--	--	--	--	-------

Rate including labour cess					1875.33
----------------------------	--	--	--	--	---------

Say Rs.1875.30 Each

Item No.	Description	Unit	Qty	Rate	Rate Code.	Cost Rs.
15.51	Dismantling or road gully chamber or various sizes including C.I. grating with frame including stacking of useful materials near the site and disposal of unserviceable materials into municipal dumps within 50 metres lead including refilling the excavated					
	Details of cost for one chamber					
	Dismantling cement concrete 1:5:10					
	1.05x1.00x0.15 m = 0.16 cum					
	Dismantling brick work in cement mortar 2.70					
	x0.20 x 0.45 = 0.24 cum					
	Dismantling cement concrete 1.2:4 2.70x0.20x0.15					
	m = 0.08 cum					
	Labour:					
	Beldar	per day	0.140	306.000	(0114)	42.840
	Coolie	per day	0.090	318.000	(0115)	28.620
	Sundries :-	1 time	0.260	2.120	(9999)	0.551
	Beldar	per day	0.250	306.000	(0114)	76.500
	Coolie	per day	0.22	318.000	(0115)	69.960
	Sundries :-	1 time	0.52	2.120	(9999)	1.102
	Beldar	per day	0.13	306.000	(0114)	39.780
	Coolie	per day	0.06	318.000	(0115)	19.080
	Sundries for scaffolding etc.	1 time	0.39	2.120	(9999)	0.827
	Dismantling C.I. grating	1 time	7.15	2.120	(9999)	15.158
	Total					294.418
	Ada tor water cnarges @ 1%					2.944184
	Total					297.362584 (X)
	Add GST 12% on "X" (multiplying factor 0.1405)					41.78
	Total					339.14 (Y)
	Add 15 % Contractor's profit and overheads on "Y"					50.87
	Cost of 1 each					390.013
	Add labour cess @ 1%					3.90
	Rate including labour cess					393.91

Say Rs.393.90 Each

15.52 Dismantling of flushing cistern of any size including stacking of useful materials near the site and disposal of unserviceable materials within 50 metres lead.

Details of cost for one

Labour:

Fitter	per day	0.25	420.00	(0116)	105.00
Beldar	per day	0.5	306.000	(0114)	153.00
Sundries	1 time	17.94	2.120	(9999)	38.03
Total					296.03
Ada tor water cnarges @ 1%					2.96
Total					298.99 (X)
Add GST 12% on "X" (multiplying factor 0.1405)					42.01
Total					341.00 (Y)
Add 15 % Contractor's profit and overheads on "Y"					51.15
Cost of 1 each					392.15
Add labour cess @ 1%					3.92
Rate including labour cess					396.07

Say Rs.396.10 Each







128



BCD/SOR_11th Edition_2022

Item No.	Description	Unit	Qty	Rate	Rate Code.	Cost Rs.
15.53	Dismantling of C.I. sluice valve including stacking of useful materials within a lead of 50 metres.					
15.53.1	Upto 150 mm dia .					
	Details of cost for dismentling 10 sluice valves (avg.) 100 mm					
	Labour:					
	Fitter	per day	0.6	420.00	(0116)	252.00
	Asst. fitter	per day	0.4	369.00	(0117)	147.60
	Beldar	per day	1.6	306.000	(0114)	489.60
	Sundries for removing the R.C.C. cover etc. for dismantling sluice value	1 time	89.7	2.120	(9999)	190.16
	Total					1079.36
	Ada tor water cnarges @ 1%					10.79
	Total					1090.16 (X)
	Add GST 12% on "X" (multiplying factor 0.1405)					153.17
	Total					1243.32 (Y)
	Add 15 % Contractor's profit and overheads on "Y"					186.50
	Cost of 10 nos					1429.82
	Cost of 1 nos					142.98
	Add labour cess @ 1%					1.43
	Rate including labour cess					144.41
	Say			Rs.144.40	Each	
15.53.2	Above 150 mm diameter					
	Details of cost for dismentling 10 sluice valves (avg.) 250 mm					
	Labour:					
	Fitter	per day	2.4	420.00	(0116)	1008.000
	Ass.Fitter	per diiy	1.54	369.00	(0117)	568.260
	Beldar	per day	6.4	306.000	(0114)	1958.400
	Sundries for removing shs R.C.C. cover etc. for dismantling sluice vale	1 time	89.700	2.120	(9999)	190.164
	Total					3724.824
	Ada tor water cnarges @ 1%					37.24824
	Total					3762.07224 (X)
	Add GST 12% on "X" (multiplying factor 0.1405)					528.57
	Total					4290.64 (Y)
	Add 15 % Contractor's profit and overheads on "Y"					643.60
	Cost of 10 nos					4934.240
	Cost of 1 nos					493.42
	Add labour cess @ 1%					4.93
	Rate including labour cess					498.35
	Say			Rs.498.40	Each	
15.54	Dismantling of spindle fire hydrant including stacking of useful materials within 50 metres lead					
	Details Of cost for 10 Nos.					
	Labour:					
	Fitter	per day	1.500	420.000	(0116)	630.000
	Asst. Fitter	per day	1.000	369.000	(0117)	369.000
	Beldar	per day	4.000	306.000	(0114)	1224.000
	Total					2223.000
	Ada tor water cnarges @ 1%					22.23
	Total					2245.23 (X)
	Add GST 12% on "X" (multiplying factor 0.1405)					315.45
	Total					2560.68 (Y)
	Add 15 % Contractor's profit and overheads on "Y"					384.10

Item No.	Description	Unit	Qty	Rate	Rate Code.	Cost Rs.
	Cost of 10 nos					2944.79
	Cost of 1 nos					294.479
	Add labour cess @ 1%					2.94
	Rate including labour cess					297.42
	Say Rs.297.40 Each					
15.55	Dismantling of cement concrete platform along with curtain wall and base concrete etc. including stacking of useful materials near the site and disposal of unserviceable materials within 50 metres lead.					
15.55.1	120x120 cm(outside to outside)					
	Details of cost for one platform					
	Dismantling cement concrete 1:5:10					
	4.00x0.35x0.12m=0.168 cum					
	0.80x0.80x0.07m=0.048 cum					
	0.216 cum					
	Say 0.22 cum					
	Dismantling brick work in cement mortar					
	4.00x0.20x0.30m=0.24 cum					
	4.40x0.10x0.20m=0.088 cum					
	0.328 cum					
	Say 0.33cum					
	Dismantling 40 mm C.C. flooring 1:2:4					
	1.00x1.00x0.04 m =0.04 cum					
	Labour:					0.000
	Beldar	per day	0.190	306.000	(0114)	58.140
	Coolie	per day	0.120	318.000	(0115)	38.160
	Sundries	1 time	0.390	2.120	(9999)	0.827
	Beldar	per day	0.350	306.000	(0114)	107.100
	Coolie	per day	0.300	318.000	(0115)	95.400
	Sundries	1 time	0.910	2.120	(9999)	1.929
	Beldar	per day	0.060	306.000	(0114)	18.360
	Coolie	per day	0.030	318.000	(0115)	9.540
	Sundries for scaffolding etc.	1 time	0.130	2.120	(9999)	0.276
	Total					329.732
	Ada tor water cnarges @ 1%					3.297316
	Total					333.028916 (X)
	Add GST 12% on "X" (multiplying factor 0.1405)					46.79
	Total					379.82 (Y)
	Add 15 % Contractor's profit and overheads on "Y"					56.97
	Cost of 1 nos					436.792
	Add labour cess @ 1%					4.37
	Rate including labour cess					441.16
	Say Rs.441.20 Each					

15.55.2 210x120 cm (outside to outside)

Details of cost for one platform

Desmantling cement concrete 1:5:10

5.80x0.35x0.22m=0.243 cum

0.80x1.70x0.075m=0.102 cum














Item No.	Description	Unit	Qty	Rate	Rate Code.	Cost Rs.
	0.345 cum					
	Say 0.35 cum					
	Dismantling of brick work in cement mortar					
	5.80x0.20x0.30m=0.348 cum					
	6.20x0.10x0.20m=0.124cum					
	0.472 cum					
	Dismantling 40 mm C.C.floor 1:2:4					
	1.90x1.00x0.04=0.08 cum					
	Labour:					
	Beldar	per day	0.31	306.000	(0114)	94.86
	Coolie	per day	0.19	318.000	(0115)	60.42
	Sundries	1 time	0.65	2.120	(9999)	1.38
	Beldar	per day	0.5	306.000	(0114)	153.00
	Coolie	per day	0.42	318.000	(0115)	133.56
	Sundries	1 time	1.3	2.120	(9999)	2.76
	Beldar	per day	0.13	306.000	(0114)	39.78
	Coolie	per day	0.06	318.000	(0115)	19.08
	Sundries for scaffolding etc.	1 time	0.39	2.120	(9999)	0.83
	Total					505.66
	Ada tor water cnarges @ 1%					5.06
	Total					510.72 (X)
	Add GST 12% on "X" (multiplying factor 0.1405)					71.76
	Total					582.47 (Y)
	Add 15 % Contractor's profit and overheads on "Y"					87.37
	Cost of 1 nos					669.84
	Add labour cess @ 1%					6.70
	Rate including labour cess					676.54

Say Rs.676.50 Each

15.55.3 320x120 cm (outside to outside)

Details of cost for one platform

Dismantling cement concrete 1:5:10

8.00x0.35x0.12 m =0.336 cum

2.80x0.80x0.075m=0.168 cum

0.504 cum

Dismantling Brick work in cement mortar

8.0x0.20x0.30m=0.48 cum

8.40x0.10x0.20m=0.168 cum

0.648 cum

Say 0.65 cum

Dismantling 40 mm C.C. flooring 1:2:4

3.00x1.00x0.04=0.12 cum

Labour:

Beldar per day 0.44 306.000 (0114) 134.64

Coolie per day 0.28 318.000 (0115) 89.04

Sundries 1 time 0.91 2.120 (9999) 1.93

Beldar per day 0.69 306.000 (0114) 211.14

Coolie per day 0.59 318.000 (0115) 187.62

Sundries 1 time 1.56 2.120 (9999) 3.31

Beldar per day 0.190 306.000 (0114) 58.14

Coolie per day 0.090 318.000 (0115) 28.62

Sundries for scaffolding etc. 1 time 0.520 2.120 (9999) 1.10

Total 715.54

Ada tor water cnarges @ 1% 7.16

Total 722.69 (X)

Item No.	Description	Unit	Qty	Rate	Rate Code.	Cost Rs.
	Add GST 12% on "X" (multiplying factor 0.1405)					101.54
	Total					824.23 (Y)
	Add 15 % Contractor's profit and overheads on "Y"					123.63
	Cost of 1 nos					947.87
	Add labour cess @ 1%					9.48
	Rate including labour cess					957.35

Say Rs.957.30 Each

15.56 Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead. .

Details of cost for 10 sqm

Beldar	per day	0.360	306.000	(0114)	110.160
Coolie	per day	0.080	318.000	(0115)	25.440
Bhishti	per day	0.070	332.000	(0101)	23.240
Sundries for scaffolding etc.	1 time	1.430	2.120	(9999)	3.032
Total					161.872
Add for water charges @ 1%					1.618716
Total					163.490316 (X)
Add GST 12% on "X" (multiplying factor 0.1405)					22.97
Total					186.46 (Y)
Add 15 % Contractor's profit and overheads on "Y"					27.97
Cost of 10 sqm					214.430
Cost of 1 sqm					21.443
Add labour cess @ 1%					0.21
Rate including labour cess					21.65

Say Rs.21.70 Per sqm

15.57 Dismantling aluminium/Cypsum partitions, doors,, windows, fixed glazing and false ceiling including disposal of unserviceable surplus material and stacking of serviceable material with in 50 m lead as directed by Engineer-in-charge. Details of cost for 10 sqm

Labour:

Carpenter II nd class	per day	0.200	369.000	(0112)	73.800
Beldar	per day	0.300	306.000	(0114)	91.800
Sundries	1 time	5.380	2.120	(9999)	11.406
Total					177.006
Add for water charges @ 1%					1.770056
Total					178.775656 (X)
Add GST 12% on "X" (multiplying factor 0.1405)					25.12
Total					203.89 (Y)
Add 15 % Contractor's profit and overheads on "Y"					30.58
Cost of 10 sqm					234.478
Cost of 1 sqm					23.448
Add labour cess @ 1%					0.23
Rate including labour cess					23.68

Say Say Rs.23.70 Per sqm










Item No.	Description	Unit	Qty	Rate	Rate Code.	Cost Rs.
----------	-------------	------	-----	------	------------	----------

BARRICADING WORK

- 15.58 (A) Providing sal ballah barricading with departmental sal ballah average 150 dia. And 2M long sal ballah post at interval of 2.5 M C/C fixed 0.5 M average below ground, packed with earth and Brick bats, well watered and rammed with three rows of average 100mm dia. Sal ballah horizontal runners fixed with iron spikes and wires, white washing one coat to exposed surface, dismantling the barricade after function, filling the holes, excluding carriage of sal ballah from and to godown up to 5K.M. lead, stacking them in countable stacks in godown including cost of all labour and materials and taxes all complete job as per specification and direction of E/I.**

Assuming 100m length of barricading**Unit per m****A Labour**

1 Digging 200mm dia and 0.5m deep holes for fixing post 40Nos at 20No holes each labour

Unskilled maz	No	2
---------------	----	---

2 Cutting Sal Ballah 2m length and 40Nos each labour

Semi skilled labour	No	1
---------------------	----	---

3 Fixing Sal Ballah in holes 40Nos @ 20No each labour

Semi skilled labour	No	2
---------------------	----	---

4 making holes in Sal Ballah and fixing spikes 40 x 3 = 120 Nos @ 30 No each carpenter

Carpenter Gr II	No	4
-----------------	----	---

5 Fixing runner with iron spikes and G.I. Wires 300m long @ 10m each labour

a Semi skilled labour	No	10
-----------------------	----	----

b Unskilled labour	No	20
--------------------	----	----

6 Watering and ramming holes 40Nos @ 20No holes each labour

a Semi skilled labour	No	2
-----------------------	----	---

7 White washing one coat to exposed surface of post 11 x

0.15 X 1.5 X 40 = 28.0m²

Runner 300 X 0.1 X p = 94.0m²

a Semi skilled labour	No	2
-----------------------	----	---

8 Dismantling and stacking at godown after the barricade work is over 1/3 of item No 3 to 5 except 4

a Semi skilled labour	No	5
-----------------------	----	---

b Unskilled labour	No	7
--------------------	----	---

Total labour

a Semi skilled labour	No	22	318.00	(0L70)	6996.000
-----------------------	----	----	--------	--------	----------

b Unskilled labour	No	29	306.00	(0L01)	8874.000
--------------------	----	----	--------	--------	----------

c carpenter Gr II	No	4	369.00	(0112)	1476.000
-------------------	----	---	--------	--------	----------

17346.000 (A)

B Material

1 Lime	Per				30.000
--------	-----	--	--	--	--------

	quntal	0.05	600.00	(1216)	
--	--------	------	--------	--------	--

2 Brick bats	m3	0.25	1322.00	(0287)	330.500
--------------	----	------	---------	--------	---------

3 Spikes	kg	12	58.00	(1219)	696.000
----------	----	----	-------	--------	---------

4 Annealed wire & sundries	1 times	65	2.12	(9999)	137.800
----------------------------	---------	----	------	--------	---------

Item No.	Description	Unit	Qty	Rate	Rate Code.	Cost Rs.
						1194.300 (B)
				Total A + B		18540.300
	Add 15% C.P and overhead charge.					2781.045
						21321.345
				Hence rate per m =		213.213
	Add labour cess @ 1%					2.130
	Rate including labour cess					215.343
				Say Per m		Rs.215.30
15.58	Demolishing R.C.C. work by mechanical means and stockpiling at designated locations and disposal of dismantled materials up to a lead of 1 kilometre, stacking serviceable and unserviceable material separately including cutting reinforcement bars.					
	Details of cost for 1 cum					
	LABOUR:					
	Mate	day	0.03	325.00	0128	9.75
	Labour for operating pneumatic tools					
	Skilled Beldar (for floor rubbing etc.)	day	0.5	369.00	0139	184.50
	Beldar	day	0.5	306.00	0114	153.00
	Labour for cutting reinforcement bars					
	Blacksmith 2nd class	day	0.5	369.00	0103	184.50
	Beldar	day	0.5	306.00	0114	153.00
	MACHINERY:					
	Air compressor 250 cfm with two leads for pneumatic cutters / hammers	day	0.125	1600.00	0040	200.00
	Tractor with trolley	day	0.05	1200.00	0039	60.00
	Joint cutting machine with 2-3 blades	day	0.125	800.00	0041	100.00
	TOTAL					1044.75
	Add Water Charges @ 1%					10.45
	Total					1055.20 (X)
	Add GST 12% on "X" (multiplying factor 0.1405)					148.26
	Total					1203.45 (Y)
	Add 15 % Contractor's profit and overheads on "Y"					180.52
	Cost of 1 cum					1383.97
	Add labour cess @ 1%					13.84
	Rate including labour cess					1397.81
				Say Per cum		Rs.1397.80
15.59	Dismantling of flexible pavement (bituminous courses) by mechanical means and disposal of dismantled material up to a lead of 1 kilometre, as per direction of Engineer-in-charge.					
	Details of cost for 1 cum					
	LABOUR:					
	Mate	day	0.01	325.00	0128	3.250
	Beldar	day	0.3	306.00	0114	91.800
	MACHINERY:					
	Tractor with trolley	day	0.048	1200.00	0039	57.600
	Tractor with tipper attachment	day	0.002	1200.00	0038	2.400
	Total					155.050
	Add Water Charges @ 1%					1.5505
	Total					156.6005 (X)
	Add GST 12% on "X" (multiplying factor 0.1405)					22.00
	Total					178.60 (Y)
	Add 15 % Contractor's profit and overheads on "Y"					26.79
	Cost of 1 cum					205.39
	Add labour cess @ 1%					2.050
	Rate including labour cess					207.443
				Say Per cum		Rs.207.40












Item No.	Description	Unit	Qty	Rate	Rate Code.	Cost Rs.
15.60	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.					
	Details of cost for 1 cum					
	Carriage of rubbish	cum	1	163.93	2264	163.930
	Add Water Charges @ 1%					1.6393
	Total					165.5693 (X)
	Add GST 12% on "X" (multiplying factor 0.1405)					23.26
	Total					188.83 (Y)
	Add 15 % Contractor's profit and overheads on "Y"					28.32
	TOTAL					217.157
	Cost of 1 cum					217.16
	Add labour cess @ 1%					2.170
	Rate including labour cess					219.327
					Say Per cum	Rs.219.30











